



CITY OF LEWISBURG FIRE DEPARTMENT

118 Water St. Lewisburg TN, 37091
Phone: (931) 359-4544
Fax: (931) 359-0082
www.lewisburgtn.gov/departments/fire



Construction Permits

105.6.6 Fire Alarm and Detection Systems

Permit Fee- (See Fee Schedule)

Permit Period- 180 Days from date of issuance.

Where Required

In accordance with the City of Lewisburg's enacted permitting requirements. A construction permit is required for the installation of or modification to fire alarm and detection systems and related equipment. Maintenance performed in accordance with this code is not considered to be a modification and does not require a permit.

Permit Application

- Application must be submitted to LFD Station 1 118 Water St. Lewisburg TN 37091.
- No work may be performed until plans have been reviewed and approved.
- Inspections are required for all permits.

Plan Review Submittal Requirements

1. Completed permit application signed by licensed alarm contractor.
2. Scope of work to be performed.
3. Type of system to be installed.
4. Detailed system plans to be submitted in person or electronically. (2 copies required for paper version)
 - a. Type and number of all devices to be installed.
 - b. Square footage of the building indicated on the plans.
 - c. Cut sheets for all components to be installed.
 - d. Specific details regarding the monitoring of the system including type of transmission means and name/location of receiving station.
 - e. All wiring information shown on the plans including size, type, and all point-to-point wire runs.
 - f. Complete battery calculations that clearly note the battery size to be provided.
 - g. Voltage drop calculation for notification devices shall be provided.
 - h. Letter of design certification indicating that the system design as submitted meets all local requirements and standards set forth by NFPA.

Required Inspections

1. Fire alarm rough-in inspection.
 - a. Verify the following:
 - i. Proper wiring being used.
 - ii. Proper wire gauge.
 - iii. Verify support of all conduit and boxes, including protective bushings in conduit.
 - iv. Verify support of all wiring is per NFPA 72 and NEC (National Electric Code).
 - v. Verify location of all fire alarm system devices.
 - vi. Verify location of fire alarm panel.
 - vii. Verify location of remote annunciator panel(s).
 - viii. Verify proper separation of wiring. (A minimum of four feet separation on horizontal runs and one foot separation on vertical runs shall be provided.)

- b. Verify that fire alarm wiring has not been painted or damaged during installation.
 - c. Duct detectors (required in units that exceed 2000cfm or units that share an area that exceeds 2000cfm collectively) shall provide the following:
 - i. Unit shutdown on activation of the duct detector.
 - ii. On activation of the duct detector a fire alarm signal shall be sent to the fire alarm control panel.
 - iii. A ceiling remote annunciator shall be installed with a LED at ceiling level that will light up when the duct detector is activated.
 - iv. All devices shall be marked with their appropriate address at the FACP.
 - d. Verify hood suppression system wiring has been installed from kitchen exhaust hood system to FACP (where applicable).
2. Fire alarm system final and acceptance.
- a. Verify the proper location and type of all fire alarm devices.
 - b. Observe fire alarm system functional tests of all alarm devices, including duct detectors.
 - c. Observe activation of the fire alarm notification devices, including electric bell on fire sprinkler system water flow (where applicable). Alarms shall activate within 90 seconds of full flow.
 - d. Observe action tests of fire sprinkler control valves. On activation of a tamper switch, a supervisory signal (audible and visible) shall be indicated at the FACP.
 - e. Observe activation of notification appliances upon activation of kitchen hood suppression systems. (where applicable).
 - f. Verify the following during the tests:
 - i. Decibel reading of notification appliances shall be 15dB above ambient noise level.
 - ii. Verify proper size batteries are installed.
 - iii. Verify duct detectors shut down the unit and send a fire alarm signal to the FACP.
 - iv. All devices shall be marked with their appropriate address at the FACP.
 - v. Verify that all signals are received at the FACP.
 - vi. Verify that all signals are received at the remote annunciator panels.
 - vii. Verify that all signals were received at the off-site monitoring agency.

g. Fire alarm zone maps shall be located at each FACP and remote annunciator panels.

Maps shall include the following:

- i. Floorplan of the occupancy being protected.
- ii. All detection device locations
- iii. Indicate type of detection device.
- iv. “Address” or zone of the detection device.
- v. The map shall be properly mounted to the wall and measures shall be taken to protect the map from damage or vandalism.